

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten, 06/2013-14, Date:05.11.2013

ITEM NO: 28

SCHEDULE-B

NAME OF WORK: Improvements to Roads & Drains in 1st cross road & Church road, at Santhoshnagara, in Ward no. 13, in SSD


Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor RAVIKUMAR B T	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	147.83	122.31	Rupees One Hundred Twenty Two and Thirty One Paise Only
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	87.6	64.97	Rupees Sixty Four and Ninety Seven Paise Only
3	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement of 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	49.28	4352.93	Rupees Four Thousand Three Hundred Fifty Two and Ninety Three Paise Only
4	Removing B.S.Slab of drain and sacking. complete as per specifications.	Sqm	279.22	48.5	Rupees Forty Eight and Fifty Paise Only
5	Refixing stone slabs of drains and pointing in CM (1:3). complete as per specifications.	Sqm	279.22	67.79	Rupees Sixty Seven and Seventy Nine Paise Only
6	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including, fixing curing etc., complete as per specifications.	Sqm	41.88	332.43	Rupees Three Hundred Thirty Two and Forty Three Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	292	894.84	Rupees Eight Hundred Ninety Four and Eighty Four Paise Only

B.T. Doshi
Signature of the Contractor

[Signature]
Executive Engineer

8	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	292	791.35	Rupees Seven Hundred Ninety One and Thirty Five Paise Only
9	Providing and laying in position plain cement concrete of mix M 15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	14.6	4625.77	Rupees Four Thousand Six Hundred Twenty Five and Seventy Seven Paise Only
10	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm	672.12	1577.92	Rupees One Thousand Five Hundred Seventy Seven and Ninety Two Paise Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specifications.	Cum	235.42	73.05	Rupees Seventy Three and Five Paise Only

B.T. Ravi Kumar
Signature of the Contractor


Executive Engineer,
Dasarahalli Division,

6r